



GENERAL NOTE(S):

1. SEE BEDDING AND TRENCHING DETAIL **(303)** FOR SPECIFICATIONS ON BACKFILL OVER A PIPE.
2. NEW 8" LIMEROCK BASE SHALL BE COMPACTED TO NOT LESS THAN 98% OF MAX DENSITY AS SPECIFIED BY THE FLORIDA DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATION 200-7.2. THE WIDTH OF THE LIMEROCK BASE SHALL BE THE WIDTH OF THE PIPE TRENCH PLUS 18" ON BOTH SIDES SEE DETAIL.
3. UNLESS OTHERWISE SPECIFIED, MATERIALS AND METHODS OF OPERATION REQUIRED TO INSTALL NEW AND REPLACEMENT PAVEMENT SHALL BE IN ACCORDANCE WITH THE LATEST APPLICABLE REQUIREMENTS OF THE FLORIDA DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION.
4. PAVEMENT SHALL BE REMOVED TO NEATLY SAWED STRAIGHT EDGES.
5. THE TYPE AND THICKNESS OF NEW SURFACE MATERIAL SHALL BE CONSISTENT WITH THAT OF THE EXISTING SURFACE, BUT IN ALL CASES SHALL MEET THE MINIMUM STANDARDS ESTABLISHED BY THE PLANS AND SPECIFICATIONS.
6. THE BACKFILLING AND PAVEMENT REPLACEMENT MUST BE DONE IN ACCORDANCE WITH FDOT INDEX.

300

**BACKFILL OVER PIPE/PAVEMENT
 REPAIR DETAIL
 NTS**

