CONCRETE FOOTER
6" WIDE x 8" THICK

EDGE OF PAVEMENT

SAW CUT
ROADWAY EDGE

21'

0.5'

0.5'

SAWCUT AND
REMOVE DRIVEWAY
CORNER ENDS

MES OF HEADWALL
PER FDOT DESIGN
STANDARDS

10'

MIN 6'
(TYP)

MIN 6'
(TYP)

4" THICK CONCRETE
APRON 3000 PSI MINIMUM

MIN. 15" PIPE; APPROVED
FDOT PIPE MATERIALS ⟨1⟩

12'

KEYED NOTE(S):

⟨1⟩ IF NECESSARY, PROVIDE CULVERT WITH MITERED ENDS TO CONVEY SWALE FLOW

ABBREVIATION: MES = MITERED END SECTION

418

**CONCRETE APRON DRIVEWAY
NEW AND EXISTING**
NTS

City of
ALACHUA
public services