


NOTE(S) :

- 1) **DO NOT CUT OFF ELBOWS. ELBOWS AT EQUIPMENT LOCATIONS AND THE CONDUIT SYSTEM TRANSITION TO THIS EQUIPMENT WILL BE INSTALLED DEEPER THAN THE NOMINAL INSTALLATION DEPTH TO MEET TURN-UP REQUIREMENTS.**
- 2) **2", 4", OR 6" CONDUIT SHALL BE USED AS SHOWN ON THE SITE PLAN.**
- 3) **COMPLETE CONDUIT SYSTEM AND CONCRETE PRODUCTS FURNISHED AND INSTALLED BY CONTRACTOR.**
- 4) **FOR 6" AND 4" CONDUIT, 48" RADIUS ELBOWS ARE REQUIRED; FOR LESS THAN 4" CONDUIT, 36" RADIUS ELBOWS ARE REQUIRED.**
- 5) **PRECAST BOX SHALL BE 5000 PSI CONCRETE MADE BY SOUTHERN PRE-CAST INC. CATALOG # SPSWB0016X6 WITH SPGRUPME911 TOP OR APPROVED EQUAL.**
- 6) **PAD MOUNTED 600 AMP SWITCHGEAR WITH SMU-20 FUSE HOLDERS MADE BY S&C ELECTRIC CO. PROVIDE FUSES AS REQUIRED BY COA.**



KEYED NOTE(S):

- 1 STABILIZED LEVEL EARTH/GRADE MIN. 3-FEET ON SIDES AND 10-FEET FRONT AND REAR

533

**TYPICAL 600 AMP. PME TYPE
SWITCHGEAR INSTALLATION**
NTS

